

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:24
REG. OF DEEDS
W. J. Board

For corners in
KENT COUNTY
(County)

Located in:	Corner Code #
T 6N R 9W	J-5
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

9866

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-5	1830	GLO	Mullett	Set Post
	1941-67	Williams & Works		Held cor. 1.3' N. of Iron
	1943	Kent Co. Wit.		3/4" Iron
	1978	LCRC #1200	Jonker	1" Iron
	1991	LCRC #5772	Chettleburgh	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas Chettleburgh on 3-25-91 and was recorded per LCRC #5772.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas Chettleburgh in place of the PK Nail he found 1.3' North of an Iron Pipe. Said PK Nail checks with Williams & Works information. LCRC #1200 is for the Iron Pipe.
LCRC #5772

Nail & KC Remon. tag N. side 36" Oak	S89°E	42.13'
Nail & KC Remon. tag NE side P. Pole	S37°E	43.75'
Nail & KC Remon. tag SE side P. Pole	S37°W	58.10'
Nail & KC Remon. tag E. side P. Pole	N13°W	101.43'
Iron Pipe	South	1.3'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 Standard Kent County Monument		
Nail & KC Remon. tag N. side 36" Oak	S89°E	42.16'
Nail & KC Remon. tag NE side P. Pole	S37°E	43.75'
Nail & KC Remon. tag SE side P. Pole	S37°W	58.15'
Nail & KC Remon. tag NE side 10" Sassafras	N45°W	60.36'
Iron Pipe	South	1.3'
Iron Pipe	West	32.74'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Hubert*