

MAR 03 1998

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 9W

J-8

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat

5. Private Claims

REG. OF DEEDS

W. J. ...

97 OCT 14 AM 10:32

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10067

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Aug. 18, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

P.A. 345 1990 KENT COUNTY

PEER APPROVED 8/28/97

CHAIRMAN Harry Fisher

A. Description of original monument and accessories and/or subsequent restoration:

J-8 1830---GLO---Not Set

Williams & Works---No information

Kent Co. Wits.---No information

1987---Survey---Exxel---Shows straight N-S 1/4 line

1990---Survey---Nederveld---1/2" Rerod

24" Elm N00°E 3.60' 6" Elm S75°W 6.21' 6" Elm N90°W 19.09'

1994---Survey---Koerber---No. desc. of corner, witnesses given:

24" Walnut N00°E 3.52' 6" Hackberry S55°W 11.55'

15" Maple S00°W 44.73' 8" Maple S75°E 38.31'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-8 Found Capped Rerod (Exxel) per the following witnesses:

Fd. Nail in 27" Walnut (Elm-Nederveld) N00°E 3.56'

Fd. Nail in 6" Hickory (Elm-Nederveld) N85°W 19.18'

Fd. Nail in 8" Hackberry S55°W 11.56'

Fd. Nail in 20" Maple S00°W 44.73' Fd. Nail in 10" Maple S75°E 38.31'

Capped Rerod (Exxel) is 0.1' N. & 0.2' W. of intersection of 1/4 lines.

The Capped Rerod (Exxel) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-8 Set Standard Kent Co. Monument (Harrison) in place of the Capped Rerod (Exxel)

Nail & KC Remon. tag S. side 8" Hackberry S55°W 11.57'

Nail & KC Remon. tag W. side 20" Walnut S00°W 44.71'

Nail & KC Remon. tag N. side 10" Maple S75°W 38.36'

Nail & KC Remon. tag SE side 27" Walnut N00°E 3.53'

Rerod & cap - West 0.48'

Signed by *[Signature]*

Surveyor's Michigan License No. 30077

Date 9/25/97

