

**SURVEY & REMONUMENTATION SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
1. Public Land Survey T <u>6N</u> R <u>9W</u>	<u>J-9</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
2. Property Controlling in Section S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec. S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:24  
REG. OF DEEDS  
*Lucy J. Bond*

**9868**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-9	1830	GLO	Mullett	Set Post
	1980	LCRC #1349	Bonnema	3/4" Solid Bar
	1981	LCRC #2473	Jonker	Set Kent County Monument
	1990	LCRC #5486	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11-27-81 and was recorded per LCRC #2473

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Solid Bar he found. Said Solid Bar checks with LCRC #1349.

	LCRC #2473		LCRC #5486
Remon. tag P. Pole	S59°W 83.31'	"X" on H/W	"X" on H/W N38°W 28.54'
Remon. tag 12" Elm	N43°E 66.89'	N38°W 28.54'	SE cor. H/W S36°W 21.41'
Remon. tag 32" Maple	S72°W 85.49'		Nail & tag P. Pole S59°W 83.31'
Remon. tag 16" Maple	N77°E 97.15'	"X" on H/W	Nail & tag 12" Elm N43°E 66.88'
Remon. tag 30" Maple	S70°E 90.98'	S36°W 21.41'	Nail & tag 16" Maple N77°E 97.13'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 Standard Kent County Monument	
"X" on top of concrete headwall	N38°W 28.54'
SE corner concrete headwall	S36°W 21.41'
Nail & KC Remon. tag NW side P. Pole	S59°W 83.22'
Nail & KC Remon. tag S. side 20" Maple	N77°E 97.13'
Nail & KC Remon. tag NW side Tw. 6" Elm	N55°E 75.45'
C/L of E-W asph. rd. is 1.4' North	
On tree row North and on field line South	



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN *Harry Rubess*