

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>9W</u>	J-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 OCT 14 AM 10:32
 REG. OF DEEDS
Lucy Bond

10068

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Aug. 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-10 1830---GLO---Not Set
 Williams & Works---No information
 Kent Co. Wits.---No information

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 9/28/97
 CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-10 Established Intersection of 1/4 lines and found an E-W fence on line ±.
 No other information or occupation for this corner.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-10 Set Standard Kent Co. Monument (Harrison) at the Intersection of 1/4 lines.
 Nail & KC Remon. tag N. side 22" Willow N75°E 42.24'
 Nail & KC Remon. tag N. side Tri. 6" Maple S60°E 69.11'
 Nail & KC Remon. tag SW side Tw. 24" Maple S30°E 75.31'
 Nail & KC Remon. tag N. side 30" Willow S75°W 61.19'
 E. end E-W fence is E. 12'±

Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 9/15/97

