

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS  
 97 APR 29 AM 8:24  
 STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- |                                    |  |            |
|------------------------------------|--|------------|
| 1. Public Land Survey              | T <u>6N</u> R <u>9W</u>                | <u>K-1</u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |

**9871**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Kirk Breitels, in a field survey on Jan. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- |     |      |                  |              |                                 |
|-----|------|------------------|--------------|---------------------------------|
| K-1 | 1830 | GLO              | Mullett      | Set Post                        |
|     | 1939 | Williams & Works |              | "City Iron"                     |
|     | 1965 | Williams & Works |              | Conc. Mon. replaces "City Iron" |
|     | 1975 | LCRC #901        | Fluharty     | Conc. Mon.                      |
|     |      | Kent Co. Wit.    |              | Iron                            |
|     | 1991 | LCRC #5768       | Chettleburgh | Set Kent County Monument        |
|     | 1995 | LCRC #8290       | Byl          | Kent County Monument            |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas Chettleburgh on 3/1/91 and recorded per LCRC #5768.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.


K-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas Chettleburgh on Twp. line in place of the Conc. Monument he found. Said Conc. Monument checks with Williams & Works & LCRC #901.

<u>LCRC #5768</u>	K-13 (KC Mon.)	East 92.40'	<u>LCRC #8290</u>	K-13 (KC Mon.)	East 92.40'
KC Remon. tag E. side 9" Oak	N16°E	36.91'	Nail & tag 12" Oak	N16°E	36.95'
KC Remon. tag NW side 11" Oak	N49°E	10.89'	Nail & tag 14" Oak	N49°E	10.97'
KC Remon. tag N. side 15" Oak	S84°E	16.85'	Nail & tag 18" Oak	S84°E	16.94'
KC Remon. tag E. side 16" Oak	S01°E	27.46'	Nail & tag 18" Oak	S01°E	27.53'
KC Remon. tag S. side 19" Oak	N85°W	11.57'	Nail & tag 22" Oak	N85°W	11.59'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- K-1 Standard Kent County Monument
- |                                      |       |        |
|--------------------------------------|-------|--------|
| Nail & KC Remon. tag E. side 12" Oak | N16°E | 36.95' |
| Nail & KC Remon. tag NW side 14" Oak | N49°E | 10.91' |
| Nail & KC Remon. tag N. side 18" Oak | S84°E | 16.89' |
| Nail & KC Remon. tag E. side 18" Oak | S01°E | 27.53' |
| Nail & KC Remon. tag S. side 22" Oak | N85°W | 11.59' |
| K-13 (Kent Co. Mon.) T7N, R9W        | N90°E | 92.40' |



Signed by Kirk Breitels  
 Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97  
 CHAIRMAN Harry Kubese