

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 6N R 9W	K-4
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:26
REG. OF DEEDS
Lucy Stand

9873

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11	●	12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Jan. 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1978	LCRC #1200	Jonker	Stone
	1981	LCRC #2229	Jonker	Set Kent County Monument
	1990	LCRC #5440	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-28-81 and was recorded per LCRC #2229

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Stone he found. Said Stone checks with LCRC #1200 and Kent Co. Wit. sheet.

<u>LCRC #2229</u>	Remon. tag T. Pole	N42°E 22.93'	Face of	<u>LCRC #5440</u>
	Remon. tag 10" Poplar	S42°E 25.7'	"whistle" marker	same witnesses as LCRC #2229
	Remon. tag 15" Poplar	S10°E 22.8'	N00°E 101.5'	
	Remon. tag 12" Poplar	S45°W 22.55'		
	C/L RR tracks at rt. angle	N50°E 51.7'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4	Standard Kent County Monument
Nail & KC Remon. tag N. side T. Pole	N42°E 22.81'
Nail & KC Remon. tag NE side 14" Poplar	S42°E 25.70'
Nail & KC Remon. tag NW side 14" Poplar	S45°W 22.66'
C/L RR tracks at rt. angles	N50°E 51.75'
SW'ly corner of "whistle" marker	N00°E 101.50'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN Henry Hubers