

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
KENT COUNTY
(County)

Located in:	Corner Code #
1. Public Land Survey T 6N R 9W	K-6
T R	
T R	
T R	
2. Property Controlling in Section S T R	
S T R	
3. Miscellaneous Property in Sec. S T R	
S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:26
REG. OF DEEDS
Lucy Stoddard

9875

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6	1830	GLO	Mullett	Set Post
	1939	Kent Co. Wit.		Monument
	1946-70	Williams & Works		Concrete Monument
	1984	LCRC #4103	Rosema	Set Kent County Monument
	1990	LCRC #5442	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 12/21/84 and was recorded per LCRC #4103.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema in place of the Concrete Monument he found. Said Concrete Monument checks with Kent Co. Wit. and Williams & Works information.

LCRC #4103	LCRC #5442
Nail & tag 15" Elm N22°E 72.49'	same witnesses as LCRC #4103
Nail & tag 12" Walnut N45°E 26.65'	plus
Nail & tag 15" Cherry S06°E 86.85'	Nail & tag P. Pole N40°W 46.28'
Nail & tag 20" Oak N88°W 58.96'	Nail & tag Guy Pole N30°E 38.68'
Nail & tag Tw. 10" Oak N50°W 52.81'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Standard Kent County Monument	
Nail & KC Remon. tag SE side 24" Elm	N22°E 72.70'
Nail & KC Remon. tag SE side 20" Walnut	N45°E 26.62'
Nail & KC Remon. tag E. side 20" Cherry	S06°E 86.04'
Nail & KC Remon. tag N. side 24" Oak	N88°W 59.01'
Nail & KC Remon. tag NE side Tw. 14" Oak	N50°W 52.84'
Nail & KC Remon. tag N. side P. Pole	N40°W 46.30'
Nail & KC Remon. tag N. side Guy Pole	N30°E 38.63'
C/L gravel road North and South is West 7'±	
Fence line to East is South 3'±	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Hubert*