

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--|-------|
| 1. Public Land Survey | T <u>6N</u> R <u>9W</u> | K-7 |
| | T <u> </u> R <u> </u> | _____ |
| | T <u> </u> R <u> </u> | _____ |
| | T <u> </u> R <u> </u> | _____ |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | _____ |
| | S <u> </u> T <u> </u> R <u> </u> | _____ |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | _____ |
| | S <u> </u> T <u> </u> R <u> </u> | _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:26
REG. OF DEEDS
Lucy Standa

9876

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|---------------|---------|--------------------------|
| K-7 | 1830 | GLO | Mullett | Set Post |
| | 1963 | Kent Co. Wit. | | Monument |
| | 1980 | LCRC #1345 | Bonnema | Monument |
| | 1981 | LCRC #2231 | Jonker | Set Kent County Monument |
| | 1990 | LCRC #5443 | Starr | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10/28/81 and was recorded per LCRC #2231

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1" x 1" x 35" Solid Bar he found. Said Solid Bar checks with Kent Co. Wit. and LCRC #1345.

<u>LCRC #2231</u>		<u>LCRC #5443</u>	
Remon. tag P. Pole	S37°E 73.92'	Nail & tag P. Pole	S37°E 73.92'
Remon. tag P. Pole	N20°W 88.23'	Nail & tag P. Pole	N20°W 88.23'
Remon. tag 40" Oak	N39°W 47.0'	Nail & tag 40" Oak	N39°W 47.00'
Remon. tag 30" Oak	N36°E 46.72'	Nail & tag 16" Oak	N60°E 47.70'
C/L of "X" gravel is 7' N.		Nail & tag Tw. 16" Oak	N25°E 61.79'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-7 Standard Kent County Monument
- | | |
|--|--------------|
| Nail & KC Remon. tag SW side P. Pole | S37°E 73.92' |
| Nail & KC Remon. tag E. side P. Pole | N20°W 88.29' |
| Nail & KC Remon. tag SW side 44" Oak | N35°W 47.06' |
| Nail & KC Remon. tag SE side 24" Oak | N60°E 47.70' |
| Nail & KC Remon. tag NE side Tw. 22" Oak | N25°E 61.86' |
- On C/L of gravel road North and South
C/L of gravel road East and West is North 6'±



Signed by *Kirk Breitels*

Date 3/27/97

Surveyor's Michigan License No. 30077
P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Hubert*