

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**

Located In:	Corner Code #
1. Public Land Survey	T 6N R 9W K-8
2. Property Controlling In Section	S T R
3. Miscellaneous Property in Sec.	S T R

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:26  
REG. OF DEEDS  
*W. J. Jonker*

**9877**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8	1830	GLO	Mullett	Set Post
	1939	Kent Co. Wit.		Monument
	1980	LCRC #1345	Bonnema	Monument
	1981	LCRC #2232	Jonker	Set Kent County Monument
	1990	LCRC #5444	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10/28/81 and was recorded per LCRC #2232

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Spike in Concrete Monument he found. Said Spike and Conc. Mon. checks with Kent Co. Wit. and LCRC #1345.

LCRC #2232	LCRC #5444
Remon. tag 8" Basswood clump	S. end 12" culv. N50°E 27.30'
Remon. tag 16" Oak	N. end 12" culv. N30°E 46.90'
Remon. tag 22" Oak	E. end 18" culv. N20°E 64.00'
Remon. tag 8" Hickory	W. end 18" culv. N10°W 62.10'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Standard Kent County Monument	
South end of 12" CMP drive culvert	N50°E 37.30'
North end of 12" CMP drive culvert	N30°E 46.90'
East end of 18" CMP cross culvert	N20°E 64.00'
West end of 18" CMP cross culvert	N10°W 62.10'
On C/L N-S gravel road	



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN Harry Huber