

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|------|------|------|
| 1. Public Land Survey | T 6N | R 9W | K-12 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T R | |
| | S | T R | |
| 3. Miscellaneous Property in Sec. | S | T R | |
| | S | T R | |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 JUN -3 AM 8:11
REG. OF DEEDS
Luigi Bernal

9997

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|------|------|---------------|---------|--------------------------------------|
| K-12 | 1830 | GLO | Mullett | Set Post |
| | 1927 | Kent Co. Wit. | | 1" Iron - Mon. Box |
| | 1984 | LCRC #4066 | Jonker | Set Kent County Monument in Mon. Box |
| | 1990 | LCRC #5447 | Starr | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 12/14/84 and was recorded per LCRC #4066

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found BROKEN standard Kent Co. Mon. (Harrison) in Mon. Box per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Round Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. Removed Mon. Box & broken Kent Co. Mon. Reset Standard Kent Co. Mon. (Harrison).

LCRC #4066

- Remon. tag P. Pole N90°W 71.96'
- Remon. tag 16" Tw. Walnut N48°E 29.78'
- Remon. tag Cor. fc. post N90°E 22.23'
- Remon. tag 24" Pine S12°E 224.24'

LCRC #5447

- Nail & tag P. Pole N90°W 71.98'
- Nail & tag Tw. 16" Walnut N48°E 29.78'
- C/L N-S blacktop road - West 9'
- On field line E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Standard Kent County Monument

- | | | |
|---|-------|--------|
| Nail & KC Remon. tag S. side P. Pole | N90°W | 71.98' |
| Nail & KC Remon. tag NW side Tw. 18" Walnut | N48°E | 29.78' |
| Cut "X" top S. end conc. culv. | S45°W | 37.14' |
| Top C/L S. end 12" CMP | S10°E | 60.70' |
| C/L N-S asphalt road is 9'± West | | |
| On field division East and West ± | | |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 5/22/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 5/22/97

CHAIRMAN *Harry Huber*