

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|-------------|-------------|------------|
| 1. Public Land Survey | T <u>6N</u> | R <u>9W</u> | <u>L-6</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Aug. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-6 1830---GLO---Not Set
Williams & Works---No information
Kent Co. Wits.---No information
1985---Survey---All Points---N-S 1/4 line between N 1/4 cor. and S 1/4 cor.
1987---LCRC #4499---Nederveld---Set Capped Iron at intersection 1/4 lines
Nail in 14" Oak East 12.89' Nail in 8" Oak N30°E 12.95'
Nail in 6" Oak West 8.00' Nail in 14" Oak S10°W 17.33'
Falls on old E-W fence

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/28/97
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-6 Found Capped Rerod (Nederveld) per the following witnesses:
Fd. Nail in 16" Oak East 12.94' Fd. Nail in 10" Oak N45°E 13.00'
Fd. Nail in stump West 8.00' Fd. nail in 18" Oak S20°W 17.36'

The Capped Rerod (Nederveld) is 0.1' N. and 0.1' E. from intersection of 1/4 lines and agrees with measurements of others ±.

The Capped Rerod (Nederveld) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-6 Set Standard Kent Co. Monument (Harrison) in place of the Capped Rerod (Nederveld).
Nail & KC Remon. tag SW side 14" Oak N55°W 27.69'
Nail & KC Remon. tag E. side 10" Oak N45°E 13.04'
Nail & KC Remon. tag N. side 16" Oak S75°E 12.94'
Nail & KC Remon. tag E. side 18" Oak S20°W 17.35'

Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 9/15/97

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 OCT 14 AM 10:32
REG. OF DEEDS
[Signature]
10072

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

