

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 9:27  
REC. OF DEEDS  
*W. J. ...*

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
T6N R 9W	L-9
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**9886**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Kirk Breitels, in a field survey on Jan, 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Code	Year	Monument	Material	Description
L-9	1830	GLO	Mullett	Set Post
	1974	LCRC #633	Spicer	Set Conc. Nail
	1981	LCRC #2376	Bueche	Set Kent County Monument
	1990	LCRC #5452	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-8-81 and was recorded per LCRC #2376

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Conc. Nail he found. Said Conc. Nail checks with LCRC #633.

LCRC #2376	LCRC #5452
SE cor, headwall	same witnesses as LCRC #2376
SE cor, headwall	plus
Nail & tag 18" Oak	Nail & tag 28" Hickory
Nail & tag 4-8" Ch. Elms	S50°W 44.89'
"X" cut conc, curb	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument	Material	Distance
L-9 Standard Kent County Monument	N25°W	37.77'
SE corner conc, headwall	S35°W	37.65'
SE corner conc, headwall	S60°E	61.18'
Nail & KC Remon, tag NE side 22" Oak	N50°W	83.61'
Nail & KC Remon, tag SW side 4-14" Ch. Elms	N77°E	104.18'
"X" cut on conc, curb to golf course drive	S50°W	44.89'
Nail & KC Remon, tag SE side 30" Hickory		



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97  
CHAIRMAN [Signature]