

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T	6N	R	9W	L-10
T		R		
T		R		
T		R		
S		T	R	
S		T	R	
S		T	R	
S		T	R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 OCT 14 AM 10:32
REC. OF DEEDS
David Bond

10074

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Kirk Breitels, in a field survey on Aug. 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L-10 1830---GLO---Not Set
Williams & Works---No information
Kent Co. Wits.---No information
1983---Survey---DNR---Comp. intersection of 1/4 lines

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/28/97
CHAIRMAN David Bond

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-10 Established and field located intersection of 1/4 lines and found nothing.
Computation of 1/4 lines agree with DNR survey.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-10 Set 1" x 8' long Iron Pipe with "Kent Co. Remon." cap (swampy area) at Intersection of 1/4 lines.
Nail & KC Remon. tag E. side 3" Maple N35°W 18.20'
Nail & KC Remon. tag N. side 3" Elm S70°E 15.74'
Nail & KC Remon. tag W. side 4" Elm S05°W 45.92'
Nail & KC Remon. tag N. side 6" Maple S65°W 52.35'
Southerly edge of Pratt Lake is 50'± N. & 100'± W.
Hunting Cabin - SSE'ly 350'±



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 9/15/97