

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 9W
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

L-12

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Kirk Breitels

July 17 1997

I, Kirk Breitels, in a field survey on July 17 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-12 1830—GLO—Not Set
Williams & Works—No information
Kent Co. Wits.—No information

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/24/97

CHAIRMAN Harry Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-12 Established Intersection of 1/4 lines. Found Pinched Pipe (no documentation) at remains of fence corner for fences E-W-S to be 3.5'± S. and 4.5'± W. of Intersection of 1/4 lines. Computed dimensions and angles fit 1989 survey by Exxel.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-12 Set Standard Kent Co. Monument (Harrison) at Intersection of 1/4 lines.

Nail & KC Remon. tag S. side 36" Beech S90°W 9.92'
Nail & KC Remon. tag E. side 18" Maple S00°E 8.64'
Nail & KC Remon. tag N. side 10" Maple N85°E 28.01'
Nail & KC Remon. tag W. side 22" Hickory N15°E 20.06'
Nail & KC Remon. tag SW side 10" Maple N30°W 24.89'
Pinched Pipe - SW 5.55'

Signed by

Kirk Breitels

Surveyor's Michigan License No.

30077

Date

9/15/97



STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 OCT 14 AM 10:32
REG. OF DEEDS
Lucy Bond

10075

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												