

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

| | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T <u>6N</u> R <u>9W</u> | M-3 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:27
REG. OF DEEDS
David Spauld

9891

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | |
|-----|------|------------------|---------|--------------------------|
| M-3 | 1830 | GLO | Mullett | Set Post |
| | | Kent Co. Wit. | | No. desc. - wits. given |
| | 1951 | Williams & Works | | Iron Pipe |
| | 1985 | LCRC #4161 | | Set Kent County Monument |
| | 1990 | LCRC #5456 | Starr | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 4-1-85 and was recorded per LCRC #4161

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema in place of the 3/4" Rerod he found. Said Rerod checks with Williams & Works information and Kent Co. Wit.

| | | | |
|-------------------|--------------------------------------|------------------|-------------------|
| <u>LCRC #4161</u> | Nail & tag P. Pole N19°E 63.50' | N. edge rail | <u>LCRC #5456</u> |
| | Nail & tag P. Pole S12°E 70.62' | S. 7.29' | same witnesses as |
| | NW bolt base RR light S78°E 87.79' | A-3, 6-8 (Rerod) | LCRC #4161 |
| | SE bolt base RR light S90°W 81.56' | S. 15.24' | |
| | Nail & tag Tw. 10" Oak S64°W 122.60' | | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | | |
|-----|--|-------|---------|
| M-3 | Standard Kent County Monument | | |
| | Nail & KC Remon. tag E. side P. Pole | N19°E | 63.50' |
| | Nail & KC Remon. tag W. side P. Pole | S12°E | 70.68' |
| | NW'ly bolt conc. base RR crossing lights | S78°E | 87.79' |
| | SE'ly bolt conc. base RR crossing lights | S90°W | 79.65' |
| | Nail & KC Remon. tag N. side Tw. 12" Oak | S64°W | 122.60' |
| | 1/2" Rerod at A-3, T6N, R8W | South | 15.24' |
| | North of edge of North rail | South | 7.29' |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Hubert*