

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- |                                    |                         |       |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey              | T <u>6N</u> R <u>9W</u> | M-4   |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:27  
REG. OF DEEDS  
*Eric Spindel*

**9892**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- |     |      |            |         |                            |
|-----|------|------------|---------|----------------------------|
| M-4 | 1830 | GLO        | Mullett | Set Post                   |
|     | 1973 | LCRC #379  | Spicer  | Set "T" Iron over Monument |
|     | 1973 | LCRC #488  | Spicer  | "T" Iron                   |
|     | 1981 | LCRC #2143 | Jonker  | Set Kent County Monument   |
|     | 1990 | LCRC #5457 | Starr   | Kent County Monument       |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9-22-81 and was recorded per LCRC #2143

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron over a Conc. Monument he found. Said "T" Iron over Mon. checks with LCRC's #379 and #488.

<u>LCRC #2143</u>		<u>LCRC #5457</u>	
Remon. tag Fence Post	S71°E 31.99'	Nail & tag fence post	S71°E 31.88'
Remon. tag 12" Oak	S30°W 63.50'	Nail & tag 12" Oak	S30°W 63.43'
Remon. tag P. Pole	N61°W 74.12'	Nail & tag P. Pole	N61°W 74.06'
Iron - West 32.95'		Nail & tag 6" Poplar	N60°E 35.14'
Iron - South 26.4'		Iron - West 32.95'	Iron - South 26.36'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4 Standard Kent County Monument
- |  |       |        |
|--|-------|--------|
| Nail & KC Remon. tag SE side 16" Oak           | S30°W | 63.47' |
| Nail & KC Remon. tag S. side P. Pole           | N61°W | 74.12' |
| Nail & KC Remon. tag NW side 10" Poplar        | N60°E | 35.14' |
| Nail & KC Remon. tag S. side 12" Poplar        | S75°E | 28.99' |
| Nail & KC Remon. tag W. side 12" Poplar        | S15°E | 83.61' |
| Iron Pipe - West 32.95'                        |       |        |
| Rerod (bent) - South 26.31' (to straight part) |       |        |



Signed by *Kirk Breitels*

Date 3/27/97

Surveyor's Michigan License No. 30077

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97  
CHAIRMAN *Harry Huber*