

MAR 03 1998

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 9W

M-5

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

REG. OF DEEDS

Luigi Standa

97 APR 29 AM 8:27

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9893

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-5	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Concrete Monument
	1975	LCRC #839	Chambers	Concrete Monument
	1976	LCRC #989	Nederveid	Concrete Monument
	1981	LCRC #2142	Jonker	Set Kent County Monument
	1990	LCRC #5458	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9-23-81 and was recorded per LCRC #2142

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Concrete Monument over a stone he found. Said Concrete Monument and stone checks with Kent Co. Wit. and LCRC's #839 & #989.

LCRC #2142

LCRC #5458

Remon. tag P. Pole	N45°E 56.88'	Iron at corner	Nail/tag P. Pole	N45°E 56.88'
Remon. tag P. Pole	N56°W 76.30'	of R.O.W.	Nail/tag P. Pole	N56°W 76.30'
Remon. tag 18" Oak	S46°E 71.15'	S46°W 46.82'	Nail/tag 18" Oak	S46°E 71.26'
Remon. tag 36" Maple	N73°W 70.76'		Nail/tag 36" Maple	N73°W 70.76'
Remon. tag Guy Pole	N30°W 58.47'	"T" Iron S. 26.4'	Nail/tag Guy Pole	N30°W 58.45'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5	Standard Kent County Monument		
Nail & KC Remon. tag	SE side P. Pole	N45°E	56.88'
Nail & KC Remon. tag	N. side P. Pole	N56°W	76.30'
Nail & KC Remon. tag	SW side 24" Oak	S46°E	71.26'
Nail & KC Remon. tag	S. side 40" Maple	N73°W	71.85'
NE cor. conc. base	Tele. Box #14400	S45°W	75.60'
C/L bit. road W.	is 8'± S., C/L bit. road E.	is 22'± S.	
C/L bit. road N.	is 4'± W., C/L grav. road S.	is 4'± W.	



Signed by *Kirk Breitels*

Date 3/27/97

Surveyor's Michigan License No. 30077

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Huber*