

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T6N R 9W  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

M-9  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REG. OF DEEDS

*Lucy Stoddard*

97 APR 29 AM 8:27

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

*Seg #1  
12/3/97  
VOID see  
L.C.R.C. #10047  
9/1/97*

9896

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Kirk Breitels, in a field survey on Jan. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		1" Iron
	1974	LCRC #633	Spicer	1" Iron
	1982	LCRC #3102	Merdzinski	Set Kent County Monument
	1990	LCRC #5461	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10-15-82 and was recorded per LCRC #3102

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Solid Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #633

LCRC #3102

SW cor. conc. blk. bldg. N45°E 86.78'  
Nail & tag 32" Walnut N40°W 42.45'  
Nail & tag P&T Pole N05°E 53.30'  
Nail & tag P&T Pole S30°W 57.45'  
NW cor. frame house S40°E 89.40'

LCRC #5461

same witnesses as LCRC #3102

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Standard Kent County Monument

SW corner concrete block building	N45°E	86.78'
Nail & KC Remon. tag W. side 34" Walnut	N40°W	45.42'
Nail & KC Remon. tag W. side P & T Pole	N05°E	53.30'
Nail & KC Remon. tag E. side P & T Pole	S30°W	57.45'
NW corner frame house	S40°E	89.40'
On C/L of E-W bit. road and on tree row North		
C/L grav. rd. S. is 5'± E.		



Signed by Kirk Breitels

Date 3/27/97

Surveyor's Michigan License No. 30077

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN Hampshire