

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:27  
REG. OF DEEDS  
*Lucy Bond*

For corners in  
KENT COUNTY  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T 6N R 9W	M-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

9898

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11	1830	GLO	Mullett	Set Post
	1966	Kent Co. Wit.		1/2" Iron in Mon. Box
	1979	LCRC #3362	Bissell	1" Pipe in Mon. Box
	1995	LCRC #8873	Jonker	Set Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 12/20/95 and was recorded per LCRC #8873

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1" x 24" Pipe he found inside a Mon. Box. Said Pipe in Mon. Box checks with Kent Co. Wit. and LCRC #3362.

LCRC #8873

Nail & KC Remon. tag S. side	P. Pole	S70°E	26.23'
Nail & KC Remon. tag SE side	P. Pole	N37°E	45.72'
Nail & KC Remon. tag S. side	P. Pole	S84°W	97.90'
1/2" Pipe (A-11, Boston Twp. corner)	North		25.47'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Standard Kent County Monument in Mon. Box

Nail & KC Remon. tag S. side	P. Pole	S70°E	26.26'
Nail & KC Remon. tag SE side	P. Pole	N37°E	45.72'
Nail & KC Remon. tag S. side	P. Pole	S84°W	97.94'
1/2" Pipe (A-11, Boston Twp. corner)	North		25.47'



Signed by Kirk Breitels

Date 3/27/97

Surveyor's Michigan License No. 30077

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN Harry Huber