

**SURVEY & REMONUMENTATION**

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**

Located In:	Corner Code #
1. Public Land Survey	T 6N R 10W A-2
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

96 JUN -7 AM 8:26

REG. OF DEEDS

*W. J. Rosema*

**9143**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Apr. 5, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner Code	Year	Witness	Monument	Status
A-2	1831	GLO	Mullett	Not Set
	1964	Kent Co. Wit.		Stake
	1984	LCRC #3924	Rosema	Set Kent County Monument
	1989	LCRC #4992	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 5/30/96  
CHAIRMAN *Henry Rube*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 8/27/84 and was recorded per LCRC #3924

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema on Twp. Line in place of the 1/2" Iron he found. Said Iron checks with Kent Co. Wit.

LCRC #3924 & #4992

Nail & KC Remon. tag N. side 11" Ash	S90°W	15.99'	
Nail & KC Remon. tag E. side 36" Oak	N00°E	56.80'	KC Mon. (M-2, 6-11)
Nail & KC Remon. tag W. side 28" Oak	S01°E	54.51'	South 82.50'
Nail & KC Remon. tag S. side 28" Oak	N79°E	76.24'	
Nail & KC Remon. tag N. side dbl. 14" Maple	S71°E	8.57'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 Standard Kent County Monument

Nail & KC Remon. tag N. side 12" Ash	S90°W	15.99'
Nail & KC Remon. tag E. side 40" Oak	N00°E	56.82'
Nail & KC Remon. tag W. side 30" Oak	S01°E	54.51'
New Nail & KC Remon. tag S. side 30" Oak	N79°E	76.30'
New Nail & KC Remon. tag N. side dbl. 16" Maple	S71°E	8.88'
Kent Co. Mon. (M-2, T6N, R11W)	South	82.50'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 4/19/96