

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE 94 DEC -5 AM 9:01
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located in: Corner Code #

W. J. Bond
REG. OF DEEDS

- | | | |
|---------------------------------------|------------|-----|
| 1. Public Land Survey | T 6N R 11W | M-7 |
| | T 6N R 10W | A-7 |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

7715

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl in a field survey on Sept. 20 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7	1831	GLO	Mullett	Set Post
	1966	Kent Co. Wit.		"T" Iron in mon. box
	1973	LCRC #402	Spicer	"T" Iron in mon. box
	1981	LCRC #2164	Jonker	Set Kent County Monument in mon. box
	1987	LCRC #4530	Bueche	Reset Kent Co. Mon. after road const.
	1989	LCRC #4986	Bueche	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/26/81 and was recorded per LCRC #2145

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche at the same position as set in 1981 by Robert J. Jonker in place of the "T" in mon. box he found. Said "T" Iron checks with Kent Co. Wit. and LCRC #402.

<u>LCRC #4530</u>	NE cor. CB casting	N60°E	63.39'	LCRC #4986	Same witnesses as LCRC #4530
	SE cor. CB casting	S60°E	67.42'		

"X" cut in curb	S30°W	67.92'
"X" cut in curb	S70°W	73.60'
"X" cut in curb	N60°W	72.97'
"X" cut in curb	N25°W	78.67'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *Harry Huber*

On C/L "X" of bit. road E-W & N-S

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Standard Kent County Monument

NE cor. CB header	N60°E	63.42'
SE cor. CB header	S60°E	67.42'
Set Nail & KC Remon. tag NE side Guy Pole	N40°W	75.10'
Set Nail & KC Remon. tag NW side P. Pole	S45°W	62.21'
Set Nail & KC Remon. tag NE side P. Pole	S45°E	71.50'
Set Nail & KC Remon. tag SE side P. Pole	N55°E	67.98'
Found "X" cut's in conc. curbs per LCRC's #4530 & #4986 to be OK m/1		
On C/L "X" of bit. road E-W & N-S		

Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11/27/94

