

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T 6N	R 10W	A-8
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:44

REG. OF DEEDS

8931

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-8	1831	GLO	Not Set
	1962	Kent Co. Wit.	1" Solid Iron in Mon. Box
	1984	LCRC #3865	Set Kent County Monument in Mon. Box
	1987	LCRC #4531	Reset Kent Co. Mon. after const. in Mon. Box
	1989	LCRC #4997	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN Hans Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 7/10/84 and was recorded per LCRC #3865.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


A-8 Found standard Kent Co. Mon. per witnesses from above LCRC as set by John C. Bueche at the same location as set in 1984 by Maurice J. Rosema in place of the 1/2" Iron he found inside a Mon. Box. Said Iron checks Kent Co. Wit. and information by others.
LCRC #4531 & #4997

"X" cut in curb	N30°E	54.00'	KC Mon. (M-8, T6N, R11W)
"X" cut in curb	N35°W	55.27'	South 11.48'
"X" cut in sidewalk	S85°W	48.54'	Irons West 100.00' & 200.00'
NE cor. casting of Catch Basin	S20°E	83.37'	On C/L blkt. N-S
NW cor. casting of Catch Basin	S25°W	85.50'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 Standard Kent County Monument in Mon. Box		
"X" cut in curb	N30°E	54.00'
"X" cut in curb	N35°W	55.27'
NE cor. casting of Catch Basin	S20°E	83.35'
NW cor. casting of Catch Basin	S25°W	85.46'
C/L top of hydrant	N20°W	110.36'
W. face of N. gate post (gate #27)	S75°E	54.35'
KC Mon. (M-8, T6N, R11W)	South	11.51'
On C/L blkt. N-S		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/1/96