

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u>	R <u>10W</u>	<u>A-9</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:44

REG. OF DEEDS

8332

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-9	1831	GLO	Mullett	Set Post
	1966	Kent Co. Wit.		Mon. Box
	1984	LCRC #3863	Rosema	Set Kent County Monument in Mon. Box
	1989	LCRC #4998	Bueche	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 7/10/84 and was recorded per LCRC #3863

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema in place of the 1/2" Iron he found inside a Mon. Box. Said Iron checks with information of others. No witnesses remain.

LCRC #3863 & #4998

NE casting of Catch Basin	S66°W	92.00'	C/L top of hydr.	N29°W	101.75'
SE casting of Catch Basin	N74°W	83.93'			
C.I. Mon. (M-9, T6N, R11W)	South	11.20'			
PK Nail & Remon. tag N. side wood post	N73°E	98.99'			
PK Nail & Remon. tag N. side wood post	S59°E	89.98'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 Standard Kent County Monument in Mon. Box		
NE casting of Catch Basin	S66°W	92.08'
SE casting of Catch Basin	N74°W	84.01'
C/L top of hydr.	N29°W	101.75'
Nail & KC Remon. tag SE side P. Pole	S30°W	86.86'
SW face of walk signal post	N45°E	59.86'
Nail & KC Remon. tag NE side P. Pole	S35°E	72.26'
Kent Co. Mon. (M-9, T6N, R11W)	South	11.20'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 3/1/96