

**SURVEY & REMONUMENTATION**

FEB 14 1997

COMMISSION

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**  
(County)

Located In:	Corner Code #
1. Public Land Survey T6N R10W	B-1
T R	
T R	
T R	
2. Property Controlling in Section S T R	
S T R	
3. Miscellaneous Property in Sec. S T R	
S T R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 SEP 13 PM 12:07  
REG. OF DEEDS  
*W. J. Rosema*

9379

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on June 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1	●											
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1	1831	GLO	Mullett	Not Set
	1955	Kent Co. Wit.		Iron on fence
	1984	LCRC #3970	Rosema	Set Kent County Monument
	1989	LCRC #5157	Chettleburgh	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/22/96  
CHAIRMAN W. J. Rosema

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 9/5/84 and was recorded per LCRC #3970

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema on Twp. Line in place of the 1/2" Iron he found. Said Iron checks with Kent Co. Wit. and survey information of others ±.

LCRC #3970	LCRC #5157
Nail/tag 15" Hickory S55°E 65.75'	SW cor. gar. fnd. N00°E 96.72'
Nail/tag 10" Pine S04°E 43.34'	Nail/tag 16" Hick. S57°E 65.72'
Nail/tag 15" Pine S40°W 54.06'	Nail/tag 12" Pine S06°E 43.46'
SW cor. gar. fnd. N00°E 96.74'	Nail/tag 13" Elm S 4°W 25.39'
KC Mon. (B-13, 7-10) East 120.04'	Nail/tag 17" Pine S40°W 54.06'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Standard Kent County Monument

Nail & KC Remon. tag SW side	20" Hickory	S57°E	65.79'
Nail & KC Remon. tag W. side	14" Pine	S06°E	43.53'
New Nail & KC Remon. tag S. side	15" Elm	S84°W	25.43'
Nail & KC Remon. tag E. side	20" Pine	S40°W	54.06'
Kent Co. Mon. (B-13, T7N, R10W)	East		120.04'
C/L N-S bit. road is East 127'±			



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 8/25/96