

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

| Located In: | Corner Code # |
|-------------|---------------|
| T 6N R 10W  | B-4           |
| T R         |               |
| T R         |               |
| T R         |               |
| S T R       |               |
| S T R       |               |
| S T R       |               |
| S T R       |               |

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on July 26, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-4 1831---GLO---Not Set 1930---Williams & Works---Held E-W 1/4 line & N-S fc.
- 1951-64---Williams & Works---Iron in swamp
- 1958---Kent Co. Wit.---Iron: 12" Elm N24°E 50.40' 15" Poplar N69°W 34.60'
- 1972---LCRC #144---N.C. Jones---3/4" Pipe  
TP S40°E 25.98' 16" Tw. Maple N55°W 23.08'
- 1972---LCRC #322---Spicer---1/2" Iron  
MBT Pole S35°E 26.41' 14" Maple N60°W 23.07'
- 1980---Survey---Nederveld & Jonker---1/2" Iron  
T. Pole SE 26.58' 24" Maple NW 22.69' Iron South 33'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 7/25/96  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-4 Found 1/2" Iron Pipe in swamp per following witnesses.  
Iron South 33'  
CATV Pole S30°E 27.6' (leaning Southerly)  
Stump NW'ly 23'±  
Said Iron is 16.2' E. and 0.1' N. from intersection of 1/4 lines and agrees with measurements ± of surveys by Williams & Works, Nederveld & Jonker and Chettleburgh.

The 1/2" Iron Pipe in swamp is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-4 Set 8' long 1" Iron Pipe with "KC Remon." cap inside 4' long 1 1/2" Iron Pipe over top of original 1/2" Iron Pipe in swamp.  
Set Nail & KC Remon. tag SW side CATV Pole S30°E 27.60' (pole leaning)  
Set Nail & KC Remon. tag SE side 4" Ash N40°E 28.18'  
Set Nail & KC Remon. tag N. side dead 8" Tree S80°E 31.15'  
Iron South 33'

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 SEP 13 PM 12:06  
REG. OF DEEDS  
[Signature]

9365

Register of Deeds Stamp & File Number

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 10 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

Signed by [Signature]

Surveyor's Michigan License No. 30077

Date 8/25/96

