

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey		T 6N R 10W	B-7
		T ___ R ___	_____
		T ___ R ___	_____
		T ___ R ___	_____
2. Property Controlling in Section	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 MAR 20 AM 8:44
 REG. OF DEEDS
W. J. Bond

8935

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-7	1831	GLO	Mullett	Set Post
	1963	Kent Co. Wit.		Iron in Mon. Box
	1973	LCRC #474 & #496	Spicer	1" Iron in Mon. Box
	1981	LCRC #1581	Merdzinski	Set Kent County Monument in Mon. Box
	1994	LCRC #7088	Bueche	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
 CHAIRMAN *Henry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/18/81 and was recorded per LCRC #1581

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron Pipe he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC's #474 & #496.
LCRC #1581 & #7088

- C/L 1972-D penny embedded NW cor. conc. base for elec. box S10°W 43.19'
- SE cor. brick bldg. N10°W 147.41'
- Top C/L hydrant N76°E 128.30'
- Top C/L hydrant N80°W 172.93'
- NW cor. 5' wide sidewalk S60°E 80.09'
- Nail & KC Remon. tag W. side P. Pole S05°E 34.38'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-7 Standard Kent County Monument in Mon. Box
- C/L 1972-D penny embedded NW cor. conc. base for elec. box S10°W 43.19'
- SE cor. brick bldg. N10°W 147.38'
- Top C/L hydrant N76°E 128.25'
- Top C/L hydrant N80°W 172.90'
- Nail & KC Remon. tag W. side P.P. S05°E 34.38'
- NW cor. 5' wide conc. sidewalk S60°E 79.94'

Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 3/1/96

