

SURVEY'S  
REMONUMENTATION  
\$7.00 SEP 18 1995  
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 AM 11:50

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>6N</u> R <u>10W</u>	<u>B-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Teri J. Bond*  
REG. OF DEEDS

**8413**  
Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on June 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-12 1831	GLO		Not Set
1972	LCRC #161	Bonnema	Set "T" Iron at "X" 1/4 lines
1989	Prien & Newhoff		"Meadowbrooke Business Park" - C 1/4 corner at "X" 1/4 lines
1993	LCRC #6758	Roon	"T" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-12 Found "T" Iron per LCRC's #161 and #6758. "T" Iron is less than 0.1' off of true intersection of 1/4 lines. "T" Iron fits plat bearing and distances and survey data of others.

LCRC #161		LCRC #6758		P.A. 345 1990 KENT COUNTY	
14" Oak	NNE 4.08'	14" Ash	West 10.58'	PEER APPROVED	<u>4/27/95</u>
8" Oak	ENE 4.98'	26" Oak	N35°E 4.46'	CHAIRMAN	<i>Harry Hubert</i>
14" Oak	SSE 72.96'	16" Oak	N85°E 5.12'		
8" Ash	W 10.25'	9" Oak	N40°W 3.41'		
C/L 60" Stump	WSW 74.7'				
E-W fence	South 0.2'				

The "T" Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-12 Set Standard Kent County Monument in place of the "T" Iron.
- Fd. Nail & MDSH tag S. side 14" Ash N90°W 10.63'
  - Set Nail & KC Remon. tag SE side 26" Oak N35°E 4.48'
  - Fd. Nail & MDSH tag S. side 16" Oak N85°E 5.14'
  - Fd. Nail & MDSH tag W. side 9" Oak N40°W 3.46'
  - Set Nail & KC Remon. tag E. side 5" Maple S25°W 17.31'
  - Set Nail & KC Remon. tag NE side 5" Ash S30°E 24.03'
  - On remains of East-West fence more or less



Signed by *Kirk Breitels* Date 6/26/95  
Surveyor's Michigan License No. 30077