

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 6N R 10W	C-4
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:44

REG. OF DEEDS

8939

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 5, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4	1831	GLO	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1949	Kent Co. Wit.		Iron	PEER APPROVED 3/7/96
	1978	LCRC #1109	Bonnema	1" Iron	CHAIRMAN <i>Harry Huber</i>
	1978	LCRC #1192	Stadt	1 1/4" Iron Pipe	
	1981	LCRC #1885	Merdzinski	Set Kent County Monument	
	1994	LCRC #7093	Bueche	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 5/21/81 and was recorded per LCRC #1885

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1 1/4" Iron over a 3/4" Iron he found. Both Irons check with Kent Co. Wit. and LCRC's #1109 & #1192.

LCRC #1885	LCRC #7093
Nail/tag 14" Oak S50°W 90.55'	Nail/tag 16" Oak S50°W 90.40'
Nail/tag 12" Willow S65°W 94.4'	Nail/tag 14" Willow S65°W 94.10'
Nail/tag P & T Pole S65°E 55.63'	Nail/tag P. Pole S65°E 55.63'
Nail/tag 12" Elm N65°W 65.54'	Nail/tag 4" Locust N20°E 59.03'
Nail/tag 12" Locust N75°E 113.24'	Nail/tag 18" Locust N70°E 143.43'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 Standard Kent County Monument

Nail & KC Remon. tag NW side 16" Oak	S50°W	90.38'
Nail & KC Remon. tag SE side 14" Willow	S65°W	94.06'
Nail & KC Remon. tag SW side P. Pole	S65°E	55.67'
Nail & KC Remon. tag W. side 4" Locust	N20°E	58.98'
Nail & KC Remon. tag S. side 18" Locust	N70°E	143.04'

On C/L bit. roads E-W & S.



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96