

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T6N R10W	C-11
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:45

REG. OF DEEDS

Handwritten Signature

8943

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Feb. 14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11 1831 GLO	Mullett	Set Post
Kent Co. Wit.		Mon. Box
1972 LCRC #214	Englert	1" Pipe in Mon. Box
1974 LCRC #714	Spicer	3/4" Iron in Mon. Box
1980 LCRC #1547	Byl	Mon. Box
1981 LCRC #1584	Merdzinski	Set Kent County Monument in Mon. Box
1994 LCRC #7098	Bueche	Kent County Monument in "Water Box"

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN *Handwritten Signature*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/20/81 and was recorded per LCRC #1584

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the "T" he found inside a Mon. Box. Said "T" Iron checks with Kent Co. Wit. and LCRC's #214, #714 & #1547.

<u>LCRC #1584</u>	T.P. N50°E 38.20'	P.P. N30°W 119.29'	Nail/tag T. Pole	N50°E 38.20'
	Top C/L hydrant	N65°W 78.51'	Nail/tag P. Pole	N30°W 119.29'
	C/L steel cor. fence post	S45°W 47.14'	Top C/L fire hydr.	N65°W 78.51'
	C/L steel S. gate post	S25°E 76.26'	C/L steel fence post	S40°W 54.00'
	C/L steel cor. fence post	S65°E 59.20'	Nail/tag 10" Pine	S65°E 81.35'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Standard Kent County Monument in "Water Box"		
Nail & KC Remon. tag SE side P. Pole	N50°E	43.61'
Nail & KC Remon. tag SW side P. Pole	N30°W	119.20'
C/L top of fire hydrant	N65°W	78.59'
C/L steel fence post	S40°W	54.40'
Nail & KC Remon. tag S. side 10" Pine	S65°E	81.35'
Set Nail & KC Remon. tag NE side 24" Pine	S35°E	90.32'
On C/L roads N-S & E-W ±		



Signed by *Handwritten Signature*
Surveyor's Michigan License No. 30077

Date 3/1/96