

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>10W</u>	<u>D-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:45
REG. OF DEEDS
Lucy Stand

8950

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Feb. 5, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13	1831	GLO	Mullett	Set Post
	1959	Kent Co. Wit.		3/4" Iron
	1972	LCRC #341	Spicer	3/4" Iron
	1981	LCRC #1693	Merdzinski	Set Kent County Monument
	1994	LCRC #7106	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
CHAIRMAN *Harry Hester*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/23/81 and was recorded per LCRC #1693

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Iron over another 3/4" Iron he found. Both Irons check with Kent Co. Wit. and LCRC #341.

LCRC #1693 & #7106

Nail & KC Remon. tag NW side 24" Maple	S55°W	48.70'	KC Mon. N 1/4 Sec. 5-5-10
Nail & KC Remon. tag N. side 22" Maple	S75°W	104.30'	West 38.91'
Nail & KC Remon. tag S. side 26" Maple	N70°W	79.84'	
Nail & KC Remon. tag E. side 18" Maple	North	26.48'	
Nail & KC Remon. tag SE side 14" Maple	N50°E	38.39'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Standard Kent County Monument

Nail & KC Remon. tag NW side 24" Maple	S55°W	48.80'
Large Nail N. side 22" Maple	S75°W	104.30'
Large Nail S. side 26" Maple	N70°W	79.92'
Nail & KC Remon. tag E. side 18" dead Maple	N00°E	26.43'
Nail & KC Remon. tag SE side 14" dead Maple	N50°E	38.31'
Kent County Mon., N 1/4 Sec. 5-5-10	West	38.93'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96