

SURVEY &
REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey

T 6N R 10W	E-1
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 JUN -7 AM 8:26

REG. OF DEEDS

9147

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-1	1831	GLO	Mullett	Set Post
	1927	Kent Co. Wit.		1" Iron
	1976	LCRC #933	Bonnema	1" Iron
	1984	LCRC #3973	Rosema	Set Kent County Monument per WW wits.
	1989	LCRC #5154	Chettleburgh	Reset Kent County Monument
	1990	LCRC #5572	Bueche	Reset Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 5/30/96

CHAIRMAN Kerry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 9/18/84 and was recorded per LCRC #3973

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
E-1 Found Kent Co. Mon. (Harrison) per wit. from above LCRC as set by John C. Bueche on Twp. line at the same location as set by Maurice J. Rosema at location he described.
LCRC #5572

Nail & KC Remon. tag NW side 24" Oak	N45°E	54.78'
Nail & KC Remon. tag SE side 10" Oak	S45°W	36.28'
W. corner brick pillar at gate	N80°E	45.50'
S. corner brick pillar	N25°E	2.49'
W. corner brick pillar	N65°W	16.54'
KC Mon. (SE cor. 32-7-10)	East	70.55'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

E-1 Standard Kent County Monument		
Nail & KC Remon. tag SE side 12" Oak	S45°W	36.28'
W. corner brick pillar (at gate)	N80°E	45.50'
S. corner brick pillar	N25°E	2.49'
W. corner brick pillar	N65°W	16.54'
W. corner brick pillar (in median)	N70°E	30.40'
KC Mon. (SE cor. 32-7-10)	East	70.58'



Signed by Kirk Breitels

Surveyor's Michigan License No. 30077

Date 4/19/96