

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T 6N R 10W	E-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:15

REG. OF DEEDS

8955

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Kirk Breitels, in a field survey on Feb. 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-6	1831	GLO	Mullett	Set Post
	1960	Kent Co. Wit.		Concrete Monument
	1974	LCRC #700	Spicer	1/2" Iron in Mon. Box
	1981	LCRC #1587	Merzinski	Set Kent County Monument in Mon. Box
	1994	LCRC #7111	Bueche	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/27/81 and was recorded per LCRC #1587

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron Pipe he found inside a Mon. Box. Said Iron Pipe checks with Kent Co. Wit. and LCRC #700
LCRC #1587 (Nail & tag in all)

14" Oak N80°W 47.95'	8" Cherry N30°W 86.27'	LCRC #7111	Nail/tag 18" Oak	N80°W 47.72'
6" Oak S40°W 65.36'	P. Pole S35°W 57.39'		Nail/tag P. Pole	S35°W 57.39'
P, T, Lt. Pole S50°E 71.38'			Nail/tag P, T, Lt. Pole	S50°E 71.38'
Guy Pole N65°E 66.87'	Iron N90°W 50.00'		Nail/tag Guy Pole	N65°E 66.87'
			1/2" Iron Pipe	N90°W 50.00'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag S. side 18" Oak	N80°W 47.72'
Nail & KC Remon. tag NW side P. Pole	S35°W 57.34'
Nail & KC Remon. tag SW side Util. Pole	S50°E 71.36'
Nail & KC Remon. tag NW side Guy Pole	N65°E 66.81'
Set Nail & KC Remon. tag top guard rail post	N25°E 74.31'
On C/L asph. road N-S & E	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 3/1/96