

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 MAR 20 AM 8:45
 REC. OF DEEDS
W. J. [Signature]

For corners in
KENT COUNTY
(County)

| | | | |
|------------------------------------|------------|---------------|-----|
| Located In: | T 6N R 10W | Corner Code # | E-7 |
| | T R | | |
| | T R | | |
| | T R | | |
| | T R | | |
| 1. Public Land Survey | | | |
| 2. Property Controlling in Section | S T R | | |
| 3. Miscellaneous Property in Sec. | S T R | | |

8956

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | |
|-----|------|---------------|--------------|--------------------------|
| E-7 | 1831 | GLO | Mullett | Set Post |
| | | Kent Co. Wit. | | 1/2" Iron |
| | 1973 | LCRC #470 | Spicer | 3/4" Iron |
| | 1981 | LCRC #1888 | Merdzinski | Set Kent County Monument |
| | 1986 | LCRC #4395 | Chettleburgh | Kent County Monument |
| | 1994 | LCRC #7112 | Bueche | Kent County Monument |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 6/2/81 and was recorded per LCRC #1888

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #470.

| | |
|---|---|
| <u>LCRC #1888 (Nail & tag)</u> | <u>LCRC #4395 & #7112 (Nail/tag)</u> |
| MBT Pole East 48.40' 12" Oak N50°E 57.99' | MBT Pole East 48.40' 14" Oak N50°E 57.85' |
| 16" Oak N20°W 62.09' 12" Oak N85°W 34.0' | 16" Pine N50°E 78.14' |
| 8" Oak S25°W 49.30' | NE cor. CB casting S25°W 31.48' |
| 12" Basswood S55°E 47.27' | NW cor. CB casting S41°E 41.64' |
| | C/L Manhole S10°E 32.45' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Standard Kent County Monument

| | | |
|---|-------|--------|
| Nail & KC Remon. tag S. side MBT Pole | East | 48.40' |
| Nail & KC Remon. tag NW side 14" Oak | N50°E | 57.85' |
| Nail & KC Remon. tag NW side 16" Pine | N50°E | 78.14' |
| NE corner catch basin casting | S25°W | 31.48' |
| NW corner catch basin casting | S41°E | 41.64' |
| C/L Manhole | S10°E | 32.45' |
| C/L bit. road North-South is East 8.3'± | | |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96