

**SURVEY &
REMONUMENTATION**

FEB 14 1997

COMMISSION KENT COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
KENT COUNTY
(County)

Located in:	T6N R10W	Corner Code #	F-7
	T___ R___		_____
	T___ R___		_____
	T___ R___		_____
	T___ R___		_____
2. Property Controlling in Section	S___ T___ R___		_____
	S___ T___ R___		_____
3. Miscellaneous Property in Sec.	S___ T___ R___		_____
	S___ T___ R___		_____

REG. OF DEEDS

Lucy Bond

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 MAR 20 AM 8:46

8963

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7						●							
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-7	1831	GLO	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1960	Kent Co. Wit.		1/2" Pipe & Stone	PEER APPROVED <u>3/7/96</u>
	1974	LCRC #757	Spicer	Monument & Stone	CHAIRMAN <u>Harry Huber</u>
	1981	LCRC #1589	Merdzinski	Set Kent County Monument	
	1994	LCRC #7121	Bueche	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/28/81 and was recorded per LCRC #1589

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Concrete Monument he found. Said Concrete Monument checks with Kent Co. Wit. and LCRC #757.

LCRC #1589 & #7121

Nail & KC Remon. tag W. side	28" Oak	S10°W	5.10'
Nail & KC Remon. tag S. side	10" Oak	West	34.24'
Nail & KC Remon. tag NW side	10" Maple	S45°W	34.93'
Nail & KC Remon. tag SW side	12" Oak	N40°W	12.23'
Nail & KC Remon. tag W. side	18" Oak	North	14.14'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 Standard Kent County Monument

Nail & KC Remon. tag W. side	28" Oak	S10°W	5.10'
Nail & KC Remon. tag S. side	10" Oak	West	34.24'
Nail & KC Remon. tag NW side	10" Maple	S45°W	34.89'
Nail & KC Remon. tag SW side	12" Oak	N40°W	12.25'
Nail & KC Remon. tag W. side	18" Oak	North	14.14'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96