

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 6N R 10W	G-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
REGISTERED FOR RECORD

96 JUN -7 AM 8:27

REG. OF DEEDS

[Signature]

9153

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-6	1831	GLO	Mullett	Set Post
	1929	"Cascade Terrace"	plat	Concrete Monument
	1973	LCRC #619	Spicer	Concrete Monument
	1981	LCRC #1500	Merdzinski	Set Kent County Monument
	1994	LCRC #1590	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 5/30/96
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/28/81 and was recorded per LCRC #1590

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Concrete Monument he found. Said Concrete Monument checks with LCRC #619 and "Cascade Terrace."
LCRC #1590 & #7129

SE cor. frame shed	S60°W	29.04'	Nail/tag S. side 18" Oak	S75°E	16.50'
SW cor. fnd. Hse. #3189 Hayward	N30°E	34.64'			
SE cor. fnd. Hse. #3189 Hayward	N70°E	63.46'			
Nail & KC Remon. tag E. side 18" Oak	S00°E	56.45'			
Nail & KC Remon. tag S. side 10" Oak	S75°E	16.50'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6	Standard Kent County Monument				
	SE cor. frame shed	S60°W	29.04'		
	SW cor. fnd. Hse. #3189 Hayward	N30°E	34.61'		
	SE cor. fnd. Hse. #3189 Hayward	N70°E	63.46'		
	Nail & KC Remon. tag E. side 18" Oak	S00°E	56.53'		
	Nail & KC Remon. tag S. side 10" Oak	S75°E	16.50'		
	Nail & KC Remon. tag S. side 18" Oak	S75°E	16.50'		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 4/22/96