

MAY 28 1997

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

REG. OF DEEDS

Lucy St. Paul

96 OCT 19 AM 8:19

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9388

Register of Deeds Stamp & File Number

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T6N R 10W	G-7
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

Year	Description	Surveyor	Notes
G-7 1831	GLO	Mullett	Set Post
1932	Kent Co. Wit.		Conc. Mon. in fence cor.
1950	"Goodwood Plat"	E. Sproat	Set Conc. Mon. at Sec. Cor.
1958	Williams & Works		Found Conc. Mon.
1968	Survey	Medema & VanKooten	Set Post in water per plat dim.
1984	LCRC #3707	Chettleburgh	Set Kent Co. Mon. (in river)
1994	LCRC #7130	Bueche	NO MON. IN PLACE - wit. remain

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by T. Chettleburgh on 1-11-84 and was recorded per LCRC #3707.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 DID NOT FIND standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by T. Chettleburgh in place of the pieces of broken conc. mon. he found. Said pieces of conc. mon. checks with surrounding plats and dimensions. Found location of G-7 to be in the Thornapple River. Established Section line as T. Chettleburgh did in 1984 per plats and computed G-7 to be 1325.85 feet East (through plat monuments) of the SW corner of "Goodwood Plat."

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 NO MONUMENT SET AT THIS LOCATION

See LCRC # 9384 for the location of a witness monument.



Signed by

Kirk Breitels

Date 10/4/96

Surveyor's Michigan License No. 30077

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/25/96
CHAIRMAN [Signature]