

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 6N R 10W	G-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 JUN -7 AM 8:27

REG. OF DEEDS

9154

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-11 1831 GLO	Mullett	Set Post
Kent Co. Wit.		Iron
1972 LCRC #269	VanKooten	Iron
1973 LCRC #383	Spicer	1" Solid Iron
1981 LCRC #1591	Merdzinski	Set Kent County Monument
1994 LCRC #7134	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 5/30/96
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/26/81 and was recorded per LCRC #1591

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 Found BROKEN standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Axle Shaft he found. Said Axle Shaft checks with Kent Co. Wit. and LCRC's #269 & #383. Repaired Kent Co. Monument.

<u>LCRC #1591 (Nail/tag in trees)</u>	<u>LCRC #7134</u>
10" Maple S40°E 21.75'	12" Maple N85°E 37.63'
18" Maple N50°E 25.24'	PK Nail 10" Ash S55°E 41.22'
Twin 14" Maple N50°W 21.24'	PK Nail 12" Maple N55°E 39.57'
14" Maple N75°W 28.62'	PK Nail 12" Ash S20°W 33.59'
14" Maple S45°W 50.43'	Nail/tag 16" Maple N50°W 21.03'
	Nail/tag 16" Maple N75°W 28.75'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 Standard Kent County Monument

Set Nail & KC Remon. tag W. side 15" Elm	S20°W 33.58'
Set Nail & KC Remon. tag SW side 15" Elm	S55°E 41.23'
Set Nail & KC Remon. tag SW side 18" Maple	N50°E 39.48'
Set Nail & KC Remon. tag N. side 12" Maple	S90°W 22.58'
Set Nail & KC Remon. tag W. side 15" Elm	N00°E 50.87'
10'± W. of bit. path	
50'± N. of bit. road	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 5/8/96