

**SURVEY & REMONUMENTATION**

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

*Handwritten signature*

96 MAR 20 AM 8:46

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
T6N R10W	G-12
T___ R___	_____
T___ R___	_____
T___ R___	_____
T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____

8973

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-12	1831	GLO	Mullett	Set Post
	1973	LCRC #467	Spicer	1/2" Solid Iron
	1981	LCRC #1592	Merdzinski	Set Kent County Monument
	1994	LCRC #7135	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/7/96  
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/28/81 and was recorded per LCRC #1592

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Solid Rod he found. Said Solid Rod checks with LCRC #467 and previous surveys.

- LCRC #1592 & #7135
- Nail & KC Remon. tag W. side 16" Maple N25°E 9.35' Nail & KC Remon. tag SW side 14" Maple S40°E 19.40'
  - Nail & KC Remon. tag S. side 10" Maple N75°W 21.76'
  - Nail & KC Remon. tag S. side 36" Maple S65°W 48.43' Face of fence chain link post for fences S & E S05°E 20.1'
  - Nail & KC Remon. tag W. side 16" Maple S05°W 29.05' 2.3' W. of N-S chain link fc.
  - Nail & KC Remon. tag S. side 12" Maple East 13.06'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-12 Standard Kent County Monument
- Nail & KC Remon. tag W. side 18" Maple N25°E 9.35'
  - Nail & KC Remon. tag S. side 12" Maple N75°W 21.76'
  - Nail & KC Remon. tag S. side 36" Stump S65°W 48.47'
  - Nail & KC Remon. tag W. side 18" Maple S05°W 28.95'
  - Nail & KC Remon. tag S. side 14" Maple East 13.06'
  - Nail & KC Remon. tag SW side 16" Maple S40°E 19.40'
  - Chain link fence cor. North & East - South 20'
  - Chain link fence N-S is West 2.3'± Cor. behind #7304 Kilmer



Signed by *Kirk Breitels*

Date 3/1/96

Surveyor's Michigan License No. 30077