

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 6N R 10W	H-13
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 JUN -7 AM 8:27

REG. OF DEEDS

9156

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1949	Williams & Works		Set Iron 56.76' E. of H-1 T5N, R10W
	1984	LCRC #3817	Chettleburgh	Set Kent County Monument
	1991	LCRC #6093	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 5/30/96
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas Chettleburgh on 12/28/83 and recorded per LCRC #3817

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas Chettleburgh in place of the Angle Iron over a 5/8" Iron he found. Both Irons check with Kent Co. Wit. and Williams & Works information.

<u>LCRC #3817 (Nail/tag in trees)</u>	<u>LCRC #6093 (Nail/tag in trees)</u>
31" Oak N02°E 34.98'	28" Oak N35°E 28.07'
25" Oak S71°E 66.30'	30" Oak N35°E 28.07' Kent Co. Mon.
15" Oak N74°W 68.77'	28" Oak S70°E 66.34' H-1 (5-10)
39" Cher. S65°E 35.95'	26" Walnut S85°W 94.91' West 56.76'
H-1 (5-10)	16" Oak N73°W 68.76'
23" Maple S82°W 94.89'	20" Hick. N45°W 53.31'
West	
20" Hick. N46°W 53.33'	
56.76'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument

Nail & KC Remon. tag SE side	32" Oak	N35°E	28.09'
New Nail & KC Remon. tag N. side	30" Oak	S70°E	66.38'
Nail & KC Remon. tag S. side	28" Walnut	S85°W	94.95'
Nail & KC Remon. tag N. side	18" Oak	N73°W	68.81'
Nail & KC Remon. tag NE side	22" Hickory	N45°W	53.31'
Kent Co. Mon. (H-1, T5N, R10W)	West	56.76'	
Capped Iron - West	18.09'		
C/L grav. rd. N. is W.	27'±	C/L grav. rd. S. is W.	53'±
Mon. is 3'± S. of C/L to E.			



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 4/19/96