

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

SEP 03 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 10W I-3

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-3	1831	GLD	Mullett	Set Post
		Kent Co. Wit.		Iron & Stones
	1973	LCRC #575	Spicer	"T" Iron
	1981	LCRC #1595	Merdzinski	Set Kent County Monument
	1989	LCRC #5070	Bueche	Set Kent County Monument
	1991	LCRC #6071	Unema	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/2/81 and was recorded per LCRC #1595

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the "L" Iron he found. Said "L" Iron checks with Kent Co. Wit. and LCRC #575.

<u>LCRC #1595</u>			<u>LCRC #5070 & #6071</u>	
Nail/tag 20" Oak	S05°W	39.20'	Nail/tag 24" Oak	S03°W 39.16'
Nail/tag P. Pole	N35°W	46.64'	Nail/tag P. Pole	N42°W 46.55'
Nail/tag 14" Oak	N10°E	36.13'	Nail/tag 18" Oak	N11°E 36.09'
Nail/tag 16" Oak	N80°E	53.85'	Nail/tag 24" Oak	N72°E 69.45'
Nail/tag 8" Pine	S75°W	68.97'	Nail/tag P. Pole	S72°W 77.62'


The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 Standard Kent County Monument

New Nail & KC Remon. tag W. side 27" Oak	S03°W	39.16'
Nail & KC Remon. tag E. side P. Pole	N42°W	46.60'
New Nail & KC Remon. tag E. side 22" Oak	N11°E	36.09'
New Nail & KC Remon. tag S. side 27" Oak	N72°E	69.42'
Nail & KC Remon. tag N. side P. Pole	S72°W	77.62'

On C/L blacktop road E-W and on C/L tree row South



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/1/96

REGISTER OF DEEDS
8979
Register of Deeds Stamp & File Number

56 MAR 20 11 01 AM
RECORDED

