

# SURVEY & REMONUMENTATION

SEP 03 1999

## KENT COUNTY REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**  
**KENT COUNTY**  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 6N R 10W	I-4
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REG. OF DEEDS

RECEIVED

SEP 20 11 04 45

8980

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	0	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

I-4	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1972	LCRC #271	VanKooten	Iron
	1972	LCRC #340	Spicer	1 1/2" Iron
	1981	LCRC #1596	Merdzinski	Set Kent County Monument
	1991	LCRC #6072	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96  
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/17/81 and was recorded per LCRC #1596

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Iron and Axle Shaft he found surrounded by stones. Said Iron and Axle Shaft checks with Kent Co. Wit. and LCRC's #271 & #340.

<u>LCRC #1596 (Nail/tag)</u>	<u>LCRC #6072</u>
16" Hickory East 52.55'	Nail/tag 18" Hickory East 52.52'
20" Pine S40°W 43.63'	Nail/tag 20" Pine West 29.99'
18" Pine West 30.04'	Nail/tag 24" Pine S40°W 43.70'
18" Pine N40°W 44.95'	Nail/tag 17" Walnut N42°W 38.03'
22" Walnut East 18.76'	Nail/tag P. Pole N70°W 47.74'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

<b>I-4 Standard Kent County Monument</b>			
Nail & KC Remon. tag S. side 20" Hickory	East	52.52'	
Nail & KC Remon. tag S. side P. Pole	N70°W	47.74'	
SE'ly cor. CB header at back curb	S35°W	78.73'	
N'ly cor. CB header at back curb	S65°W	35.74'	
Concrete Monument	West	43.02'	
C/L Buttrick Ave. - East 1'± and on tree row East			



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 3/1/96