

FEB 14 1997

KENT COUNTY REMONUMENTATION

Commissioner

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 MAR 20 AM 8:47  
REG. OF DEEDS  
*Lucy Bond*

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 10W

I-10

T R

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

8984

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Feb. 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10	1831	GLO	Mullett	Set Post
	1933	Kent Co. Wit.		Witnesses given
	1972	LCRC #153	Bonnema	Bolt Spike
	1972	LCRC #268	VanKooten	Bolt Spike
	1982	LCRC #2742	Merdzinski	Set Kent County Monument
	1991	LCRC #6078	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/2/96  
CHAIRMAN *Frank Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/22/82 and was recorded per LCRC #2742

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Bolt Spike, Iron Pipe, Stone, Pop Bottles he found. All check with Kent Co. Wit. and LCRC's #153, 268.

<u>LCRC #2742</u>	<u>LCRC #6078</u>
Nail/tag P & T Pole N60°W 116.90'	same witnesses ±
Nail/tag 30" Oak N45°E 63.47'	
Nail/tag 18" Oak S70°E 76.05'	
Nail/tag 16" Ash S50°W 33.27'	
C/L of USGS Mon. S10°E 32.50'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Standard Kent County Monument	
Nail & KC Remon. tag NE side P. Pole	N60°W 116.95'
Nail & KC Remon. tag SE side 33" Oak	N45°E 63.48'
Nail & KC Remon. tag SE side 24" Ash	S50°W 33.23'
C/L of USGS Monument	S10°E 32.50'
Set Nail & KC Remon. tag NE side 8" Oak	S45°E 46.17'
Mon. 0.5'± N. E-W asph. rd. and on C/L grav. rd. N. ±	



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/1/96