

FEB 14 1997

**KENT COUNTY REMONUMENTATION**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**  
(County)

Located In:	Corner Code #
T 6N R 10W	J-11
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 MAR 20 AM 8:47  
REG. OF DEEDS  
8987  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-11	1831	GLO	Mullett	Set Post
	1962	Kent Co. Wit.		"X" in conc.
	1972	LCRC #113	Spicer	3/4" Iron in Mon. Box
	1981	LCRC #1600	Merdzinski	Set Kent County Monument in Mon. Box
	1991	LCRC #6086	Unema	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/7/96  
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/26/81 and was recorded per LCRC #1600

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron Pipe he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #113.

LCRC #1600 (Nail/tag in trees-poles)	LCRC #6086
PP N60°E 64.21'	G. Pole N90°E 29.22'
28" Maple N20°E 96.88'	Nail/tag 32" Maple N20°E 96.81'
Util. Pole S80°W 32.27'	Nail/tag P. Pole N55°E 64.18'
18" Ash S35°E 53.55'	Nail/tag 20" Elm S35°E 53.67'
18" Maple S20°W 83.52'	Nail/tag 20" Maple S19°W 83.50'
	Nail/tag P. Pole S84°W 32.25'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag W. side 36" Maple	N20°E 96.81'
New Nail & KC Remon. tag SW side 24" Elm	S35°E 53.14'
Nail & KC Remon. tag E. side 22" Maple	S19°W 83.50'
PK Nail N. side P. Pole	S84°W 32.38'
Set Nail & KC Remon. tag NW side new P. Pole	N55°E 63.40'
On C/L of Whitneyville Rd. N-S	
C/L grav. road to West (52nd St.) is 30'± North	



Signed by *[Signature]*  
Surveyor's Michigan License No. 30077

Date 3/1/96