

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:	Corner Code #
T 6N R 10W	K-1
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

REG. OF DEEDS

Lucy Bond

96 MAR 20 AM 8:47

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8989

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 22, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-1	1831	GLO	Mullett	Set Post
	1930-65	Williams & Works		Iron - Steel fence post
	1972	LCRC #207	Bonnema	1/2" Iron in rock pile
	1993	LCRC #6747	Rosema	Set Kent County Monument
	1995	LCRC #8084	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/6/96
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 1/22/93 and was recorded per LCRC #6747

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema on Twp. Line in place of the 1/2" Iron Pipe he found. Said Iron Pipe checks with Williams & Works information and LCRC #207.

LCRC #6747 & #8084

Nail & KC Remon. tag SW side 12" Oak	N42°W	10.34'	Kent Co. Mon.
Nail & KC Remon. tag S. side 24" Oak	N88°W	23.80'	(K-13, T7N, R10)
Nail & KC Remon. tag SE side 12" Walnut	S47°W	7.56'	S90°E 33.28'
Nail & KC Remon. tag E. side 12" Oak	S15°W	41.30'	
Nail & KC Remon. tag NE side 10" W. Cherry	S50°E	5.90'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Standard Kent County Monument

Nail & KC Remon. tag SW side 12" Oak	N42°W	10.34'
Nail & KC Remon. tag S. side 24" Oak	N88°W	23.82'
Nail & KC Remon. tag SE side 12" Walnut	S47°W	7.56'
Nail & KC Remon. tag E. side 14" Oak	S15°W	41.30'
Nail & KC Remon. tag NE side 10" W. Cherry	S50°E	5.90'
Kent Co. Mon. (K-13, T7N, R10)	S90°E	33.30'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96