

**SURVEY &  
REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in  
**KENT COUNTY**

(County)

Located In:	Corner Code #
T 6N R 10W	K-3
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

1. Public Land Survey

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3										●		
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

REG. OF DEEDS

*Lucy Spind*

96 MAR 20 AM 8:47

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORDING

8990

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

K-3	1831	GLO	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
		Kent Co. Wit.		Witnesses given	PEER APPROVED 3/7/96
	1978	LCRC #1110	Bonnema	3/4" Iron	CHAIRMAN <i>Harry Huber</i>
	1982	LCRC #2747	Merdzinski	Set Kent County Monument	
	1991	LCRC #6094	Unema	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/18/82 and was recorded per LCRC #2747

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Iron he found. Said Iron checks with LCRC #1110. No Kent Co. Wit. remain.

<u>LCRC #2747</u>	<u>LCRC #6094</u>
Nail/tag Twin 12" Oak S10°E 30.8'	Nail/tag 22" Oak N45°W 6.36'
Nail/tag 10" Oak S30°W 34.7'	Nail/tag 12" Oak N65°E 20.20'
Nail/tag 22" Oak N45°W 6.38'	Nail/tag 12" Oak S80°E 34.54'
Nail/tag 10" Oak N65°E 20.20'	Nail/tag Twin 12" Oak S10°E 30.82'
Nail/tag 10" Oak S80°E 34.55'	Nail/tag 12" Oak S30°W 34.68'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 Standard Kent County Monument		
Nail & KC Remon. tag S. side 26" Oak	N45°W	6.36'
Nail & KC Remon. tag SE side 14" Oak	N65°E	20.20'
Nail & KC Remon. tag N. side 14" Oak	S80°E	34.54'
Nail & KC Remon. tag E. side Twin 14" Oak	S10°E	30.82'
Nail & KC Remon. tag E. side 14" Oak	S30°W	34.68'
On old fence line E-W		



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/1/96