

**SURVEY & REMONUMENTATION**

FEB 14 1997

**KENT COUNTY REMONUMENTATION**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>10W</u>	<u>K-8</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

56 JUN -7 AM 8:27

REG. OF DEEDS

*Lucy Bond*

**9166**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Apr. 3, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1975	LCRC #855	Nederveld	Iron
	1982	LCRC #2750	Merdzinski	Set Kent County Monument
	1991	LCRC #6099	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 5/30/96  
CHAIRMAN Harry Kuberski

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/22/82 and was recorded per LCRC #2750

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wit. and LCRC #855.

<u>LCRC #2750</u>	<u>LCRC #6099</u>
Nail/tag 16" Osage Orange S85°E 33.80'	Nail/tag 18" Osage Orange S85°E 33.76'
Nail/tag 18" Ash S40°W 46.97'	Nail/tag P. Pole N21°W 84.25'
Nail/tag P. Pole N25°W 84.36'	Nail/tag 10" Spruce N37°E 57.73'
Nail/tag 6" Spruce N40°E 57.75'	Nail/tag 20" Ash S40°W 46.90'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-8 Standard Kent County Monument

Nail & KC Remon. tag N. side 22" Osage Orange	S85°E	33.76'
Nail & KC Remon. tag E. side P. Pole	N21°W	84.25'
Nail & KC Remon. tag W. side 12" Spruce	N37°E	57.73'
Nail & KC Remon. tag SE side 22" Ash	S40°W	46.93'
Mon. is on tree rows to East & West		
Mon. is 1'± East of C/L N-S bit. road		



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 4/19/96