

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in  
**KENT COUNTY**

Located In:	Corner Code #
T 6N R 10W	K-9
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 MAR 20 AM 8:47  
REG. OF DEEDS  
*Lucy Bond*  
8993  
Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9	1831	GLO	Mullett	Set Post
	1974	LCRC #856	Nederveld	Iron
	1982	LCRC #2751	Merdzinski	1/2" Solid Iron
	1991	LCRC #6100	Unema	Set Kent County Monument
				Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96  
CHAIRMAN *Harry H. H. H.*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 3/26/81 and was recorded per LCRC #2751

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the PK Nail over a 1/2" Solid Iron he found. Said PK Nail and Solid Iron checks with Kent Co. Wit. and LCRC #856.

LCRC #2751 (Nail/tag in trees-poles)	LCRC #6100 (Nail/tag in trees-poles)
32" Maple N35°W 50.06'	36" Maple N27°W 50.11'
24" Hickory N35°E 57.43	18" Hickory N38°E 57.49'
14" Hickory N75°E 106.20'	16" Hickory N77°E 106.22'
PP S60°E 110.65' PP S15°E 145.00'	PP S43°W 64.75' PP S05°E 144.86'
PP S40°W 64.87'	PP S60°E 110.67'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Standard Kent County Monument

Nail & KC Remon. tag NE side	40" Maple	N27°W	50.11'
Nail & KC Remon. tag SE side	22" Hickory	N38°E	57.49'
Nail & KC Remon. tag SE side	18" Hickory	N77°E	106.22'
Nail & KC Remon. tag SE side	P. Pole	S43°W	64.75'
Nail & KC Remon. tag E. side	P. Pole	S05°E	144.90'
Nail & KC Remon. tag NE side	P. Pole	S60°E	110.67'

Mon. is 2'± N. asph. rd. E-W and 2'± W. grav. rd. S.  
On C/L asph. rd. to N.



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/1/96