

SURVEY &  
REMONUMENTATION

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

95 MAR 20 AM 8:47

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

For corners in  
KENT COUNTY

(County)

Located In:	Corner Code #
T 6N R 10W	K-11
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

8994

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 1, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-11	1831	GLD	Mullett	Set Post
	1944	Kent Co. Wit.		3" Iron
	1974	LCRC #709	Spicer	1/2" Iron
	1981	LCRC #1895	Merdzinski	Set Kent County Monument
	1991	LCRC #6102	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/7/96  
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 5/19/81 and was recorded per LCRC #1895

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron over a 3" Iron he found. Both Irons check with Kent Co. Wit. and LCRC #709

LCRC #1895 (nail/tag in trees-pole)	LCRC #6102 (nail/tag in trees-poles)
"+" cut culv. N10°W 96.32'	PP S35°W 72.09' 18" Maple S56°W 45.39'
NW cor. brk. hse. N30°E 146.70'	"X" cut conc. culv. N07°W 96.34'
14" Oak S45°E 32.68' PP S35°W 72.15'	18" Oak S35°E 32.57'
12" Maple S60°W 45.40'	14" Maple N33°E 112.83'
C/L 6" Maple N30°E 112.95'	NW cor. brk. hse. N46°E 146.73'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 Standard Kent County Monument	
Set Nail & KC Remon. tag NW side P. Pole	S35°W 68.81'
"X" cut on W. end conc. culv.	N07°W 96.34'
Nail & KC Remon. tag NW side 20" Maple	S56°W 45.44'
Nail & KC Remon. tag W. side 20" Oak	S35°E 32.53'
Nail & KC Remon. tag W. side 16" Maple	N33°E 112.75'
NW corner brick house	N46°E 146.67'
C/L E-W asph. rd. is S. 1.3' ±	
On C/L gravel rd. N. ±	



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/1/96