

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
KENT COUNTY

Located In:	Corner Code #
(County)	
1. Public Land Survey	T 6N R 10W L-1
	T R
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:47

REG. OF DEEDS

Lucy St. Paul

8996

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1	1831	GLO	Mullett	Not Set
	1977	LCRC #976	Bonnema	"T" Iron
	1990	LCRC #5495	Bueche	Set Kent County Monument
	1994	LCRC #8097	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 5/24/90 and was recorded per LCRC #5495.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche on Twp. Line in place of the 1/2" Rerod over a "T" Iron he found. Both Irons checks with LCRC #976.

LCRC #5495 (same witnesses ± on LCRC #8097)

Nail & KC Remon. tag S. side 30" Oak	N85°W	18.65'	KC Mon. (L-13, 7-10)
Nail & KC Remon. tag W. side 30" Db1. Oak	S20°E	107.68'	East 16.81'
Nail & KC Remon. tag S. side 10" Locust	S70°E	52.07'	
Nail & KC Remon. tag S. side 8" Elm	N75°E	43.74'	C/L bit. N-S
Nail & KC Remon. tag E. side 6" Db1. Locust	N15°W	94.05'	East 10.5'±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Standard Kent County Monument

New Nail & KC Remon. tag S. side 30" Oak	N85°W	18.63'
New Nail & KC Remon. tag W. side 36" Db1. Oak	S20°E	107.74'
New Nail & KC Remon. tag S. side 12" Locust	S70°E	52.07'
New Nail & KC Remon. tag S. side 10" Elm	N75°E	43.74'
New Nail & KC Remon. tag E. side 8" Db1. Locust	N15°W	94.05'
Kent Co. Mon. (L-13, T7N, R10W)	East	16.71'
C/L N-S blacktop road is East 10.5'±		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/1/96