

OCT 28 1994

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
CASCADE TWP.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 JUL -5 PM 3:11

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey T 6N R 10W L-2 C 1/4 cor.
T _____ R _____ Sec. 1
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Will Byl
REG. OF DEEDS

6944

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								1
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on June 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-2 Williams & Works 1962: Est. N-S 1/4 line by using N 1/4 cor. & N-S fence South of M-21 at S/L R/W. E-W 1/4 line est. by E 1/4 cor. and fence cor. 1335.5' W. of E 1/4 cor. projected Westerly. Set iron at intersection of these lines for C 1/4 cor.

Witnesses: Exxel Eng. LCRC #976 March 8, 1977 "T" Iron

24" Oak E 47.35'	Nail in side 20" Locust NW 32.57'
Db1. 10" Locust SW 21.6'	Nail in side db1. 18" Locust SW 21.69'
10" Locust NW 32'	Nail in side 28" Oak E 48.27'
16" Oak NNE 47.2'	Nail in side 14" Oak SE 55.86'
	C/L road East 12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-2 Found "T" Iron at surface of road; found 2nd "T" iron 8" below grade; found iron pipe 12" below grade.

Fd. cut nail in side 24" Locust NW 32.49'

Fd. cut nail in side db1. 24" Oak SW 21.27'

Fd. cut nail in side 36" Oak E 48.11'

Corner "N" on recorded survey of Sections 1 & 2-6-10
Recorded survey L269 P21

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/24/94
CHAIRMAN *Harry Hubbell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-2 Replaced Irons with Standard Kent County Monument

Set Nail & KC Remon. tag NW side 24" Locust	N25°W	32.58'
Set Nail & KC Remon. tag N. side Tw. 24" Locust	S70°W	21.31'
Set Nail & KC Remon. tag S. side 36" Oak	S75°E	48.17'
Set Nail & KC Remon. tag S. side 24" Oak	S45°E	55.69'
Set Nail & KC Remon. tag W. side 18" Locust	S25°W	54.12'



Signed by *William R. Byl* Date *06/27/94*

Surveyor's Michigan License No. *23502*